



Key

- +0.30 Existing level
- +2.30 Proposed level
- G Proposed decorative surface: Excavate ground and bring to levels; supply and lay granular fill Type 1 laid to falls and compact to structural engineer's spec; lay 60mm dense macadam course; Lay Fibretec, or similar approved resin bonded gravel, to manufacturer's recommendations. Aggregate size 6-10mm; colour: golden amber.
- PG Proposed topdressing of decorative compacted gravel: 6mm-10mm aggregate size.
- M 50mm local path gravel, laid to suppliers recommendations.
- M 75mm depth coarse bark mulch, Loose fill.

- Proposed steel edging to paved areas as indicated eg 'Everedge' by Excelledge or similar.
- Proposed existing Purbeck stone boulder edging to rocky; 300-400 rocky stone blocks on concrete surrounds.
- Proposed Purbeck stone boulders for lake revetment; see dwg PPL-FL-D-300 (see Detail B1-C3).
- Proposed formal lake edge - Gabion with Purbeck stone coping. Refer to dwg PPL-FL-D-300 (see Detail A1-A3).
- Proposed informal lake edge - Gabion Revetment. Refer to dwg PPL-FL-D-300 (see Detail C1-C3).
- Proposed seat with/without backrest; straight or curved; heavy durable hardwood with a natural finish; e.g. Type 2 seat by Woodcase or similar.
- Proposed picnic benches: durable hardwood, natural finish, eg Standard picnic seat by Woodcase or similar.
- Trees to be removed - not used
- Proposed shrub, tree and ground cover planting - refer to Planting Plan and Plant Schedule for specification.
- Proposed marginal planting - refer to Plant Schedule for specification. Mix 'Lakes Marginal and Aquatic Plants'.



PROJECT  
Poole Park Life

Appendix C3  
Freshwater Lakes - Improvements  
GA

SCALE AT A1	SITE	DATE	DRAWN BY	CHECKED BY
1:250	10/01/2017	BU	BU/MW	
PROJECT NO	DRAWING NUMBER	REVISION		
PPL	FL-PL-401			
STATUS	Tender			